

Madingley Road - Cambridge



©Michael Cameron.

Hill Partnerships

Project Information

- Type of Building: 4-storey new build apartment block
Glazing System: System 600
Quantity: 27 balconies
Construction: The balconies feature on the front and side elevations of the building. The balustrade is installed on the extended concrete slab and cantilevers up to form a barrier 1100mm high. Frameless, clear laminated float safety glass in the balustrade section features four decorative powder coated aluminium horizontal railings in the design. The balcony is completed with a hardwood timber handrail. Full height glazed privacy screens are also supplied as part of the system.
Completion Date: 2006

cpd provider



©Michael Cameron.